



No: IITMandi(CW)/SE-660/2014-15/780-781

Date: 28-01-2015

**NOTICE INVITING QUOTATION**

Quotation as per schedule attached is hereby invited by the undersigned so as to reach this office on or before 03-02-2015 upto 01:00 PM and shall be opened on same day at 03:30 PM in the presence of intending contractor or their authorized representatives.

**Name of work:** Repair of existing toilets, Gutter & terrace at 1st Floor of Admin block and Gutter at Academic block at Mandi campus.

----- As Per Schedule Attached -----

**Terms & Conditions:-**

1. The work will be carried out as per CPWD General Specifications for Civil works amended up to date & as per the instructions of the Engineer-in-charge.
2. The work is of urgent nature and is to be completed within 10 days from issue of work order.
3. All damages done during execution of the work is to be made good by the contractor and nothing extra will be paid separately for the same.
4. The Prices quoted should be net and nothing extra is to be paid.
5. Contractor shall abide by labour rules and regulations.
6. All the applicable taxes shall be deducted from bill.
7. All material to be used on the work will have to be got approved from the Engineer-in-charge.

-sd-  
Superintending Engineer

**COPY TO:-**

1. IIT Mandi website.
2. Notice Board, IIT Mandi.

-sd-  
Superintending Engineer

**SCHEDULE OF QUANTITY**

<b>Name of work : -Repair of existing toilets, gutter &amp; terrace at 1st Floor of Admin block and gutter at Academic block at Mandi campus.</b>						
<b>Sr. No.</b>	<b>Description of items</b>	<b>Qty.</b>	<b>Unit</b>	<b>Rate(In Rs)</b>		<b>Amount (In Rs)</b>
				<b>(In Figure)</b>	<b>(In Word)</b>	
1	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead For thickness of tiles above 25 mm and up to 40 mm as per entire satisfaction and direction of Engineer-in-charge.	163.44	sqm			
2	Providing and laying one coat of water proofing Component (Pidilite 301) in the ratio of 1:1 with Portland cement as per entire satisfaction and direction of Engineer-in-charge.	65.00	sqm			
3	20 mm cement plaster of mix 1:4 (1 cement: 4 coarse sand) as per entire satisfaction and direction of Engineer-in-charge.	69.12	sqm			
4	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete 40 mm thick with 20 mm nominal size stone aggregate as per entire satisfaction and direction of Engineer-in-charge.	82.11	sqm			
5	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, i/c cutting and making good the walls etc. Internal work 15 mm dia nominal bore as per entire satisfaction and direction of Engineer-in-charge.	50.97	metre			
6	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete as per entire satisfaction and direction of Engineer-in-charge.	90.85	sqm			
7	Providing and fixing G.I. Union in G.I. pipe including cutting and threading the pipe and making long screws etc. complete (New work) 15 mm nominal bore as per entire satisfaction and direction of Engineer-in-charge.	4.00	each			
8	Providing and fixing PTMT soap Dish Holder having length of 138mm, breadth 102mm, height of 75mm with concealed fitting arrangements, weighing not less than 106 gms as per entire satisfaction and direction of Engineer-in-charge.	8.00	each			
9	Providing and fixing C.P. brass stop cock (concealed) of standard design and of approved make conforming to IS:8931 15 mm nominal bore as per entire satisfaction and direction of Engineer-in-charge.	8.00	each			
10	Providing and fixing PTMT towel rail complete with brackets fixed to wooden cleats with CP brass screws with concealed fittings arrangement of approved quality and colour 450 mm long towel rail with total length of 495 mm, 78 mm wide and effective height of 88 mm, weighing not less than 170 gms as per entire satisfaction and direction of Engineer-in-charge.	2.00	each			
11	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade Old work (one or more coats) as per entire satisfaction and direction of Engineer-in-charge.	118.37	sqm			
12	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade One or more coats on old work as per entire satisfaction and direction of Engineer-in-charge.	23.73	sqm			
	<b>Total</b>					