

No: IIT Mandi (CW)/SE -791/2016-17/1403-04

Date: 11-11-16

NOTICE INVITING QUOTATION

Quotation as per schedule attached is hereby invited by the undersigned so as to reach this office on or before 18-11-2016 upto 01:00 PM and shall be opened on same day at 03:30 PM in the presence of contractors or their authorized representatives who may wish to be present at the time of opening.

Name of work: Barricading of area around Faculty Apartment C6 & C7 with Barbed Wire Fencing.

----- As Per Schedule Attached -----

Terms & Conditions:-

1. The work will be carried out as per CPWD General Specifications for Civil works amended up to date & as per the instructions of the Engineer-in-charge.
2. The work is of urgent nature and is to be completed immediately within 20 days from issue of work order.
3. All damages done during execution of the work is to be made good by the contractor and nothing extra will be paid separately for the same.
4. The Prices quoted should be net and nothing extra is to be paid.
5. Contractor shall abide by labour rules and regulations.
6. All the applicable taxes shall be deducted from bill.
7. All material to be used on the work will have to be got approved from the Engineer-in-charge.

COPY TO:-

1. Notice Board.
2. Institute Website.

—sd—
Superintending Engineer

—sd—
Superintending Engineer

Schedule of Quantity

Name of work : - Barricading of area around Faculty Apartment C6 & C7 with Barbed Wire Fencing.

Sr. No.	Description of items	Qty.	Unit	Rate(In Rs)		Amount (In Rs)
				(In Figure)	(In Word)	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m all kinds of soil as per entire satisfaction and direction of Engineer-in-charge.	13.86	cum			
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) as per entire satisfaction and direction of Engineer-in-charge.	11.34	cum			
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size) as per entire satisfaction and direction of Engineer-in-charge.	2.52	cum			
4	Providing and fixing ISI marked M.S. pressed butt hinges bright finished with necessary screws etc. complete 100x58x1.90 mm as per entire satisfaction and direction of Engineer-in-charge.	12.00	Each			
5	Providing and fixing ISI marked oxidised M.S. sliding door bolts with nuts and screws etc. complete 250x16 mm as per entire satisfaction and direction of Engineer-in-charge.	3.00	Each			
6	Providing and fixing ISI marked oxidised M.S. handles conforming to IS:4992 with necessary screws etc. complete 100 mm as per entire satisfaction and direction of Engineer-in-charge.	4.00	Each			
7	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete as per entire satisfaction and direction of Engineer-in-charge.	456.00	kg			
8	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works as per entire satisfaction and direction of Engineer-in-charge.	573.08	kg			
9	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade two or more coats on new work as per entire satisfaction and direction of Engineer-in-charge.	52.40	sqm			
10	Supplying and fixing turn buckles and straining bolts for barbed wire fencing each as per entire satisfaction and direction of Engineer-in-charge.	70.00	set			
11	Fencing with angle iron post placed at required distance embedded in cement concrete blocks, every 15th post, last but one end post and corner post shall be strutted on both sides and end post on one side only and provided with horizontal lines and two diagonals interwoven with horizontal wires, of barbed wire weighing 9.38 kg per 100 m (minimum), between the two posts fitted and fixed with G.I. staples, turn buckles etc. complete. (Cost of posts, struts, earth work and concrete work to be paid for separately). Payment to be made per metre cost of total length of barbed wire used With G.I. barbed wire as per entire satisfaction and direction of Engineer-in-charge.	2179.20	mtr			
Total						